


AD-A088 042

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/13
NATIONAL DAM SAFETY PROGRAM, VERONA LAKE DAM (NJ00386), PASSAIC--ETC(U)
FEB 80 R J MCDERMOTT DACW61-79-C-0011

UNCLASSIFIED

NL

END
DATE
FILMED
9-80
DTIC



• MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

NOTICE

**THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED US BY
THE SPONSORING AGENCY. ALTHOUGH IT
IS RECOGNIZED THAT CERTAIN PORTIONS
ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.**



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO
NAFEN-N

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

11 AUG 1980

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Verona Lake Dam in Essex County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Verona Lake Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's spillway is considered inadequate because a flow equivalent to 33 percent of the Spillway Design Flood - SDF - would cause the dam to be overtopped. (The SDF, in this instance, is one half of the Probable Maximum Flood). The decision to consider the spillway "inadequate" instead of "seriously inadequate" is based on the determination that dam failure from overtopping would not significantly increase the hazard to loss of life downstream from the dam from that which would exist just before overtopping failure. To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

- a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.
- b. With the lake drawn down, the masonry spillway should be thoroughly inspected by a professional consultant engaged by the owner within six months from the date of approval of this report. Based on the inspection, together with any necessary subsoil, seepage and structural investigations, the need for remedial measures should be determined and the measures implemented.
- c. The owner should develop an emergency action plan and downstream warning system within six months from the date of approval of this report.
- d. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam within one year from the date of approval of this report.

NAPEN-N

Honorable Brendan T. Byrne

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Minish of the Eleventh District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



JAMES G. TON
Colonel, Corps of Engineers
District Engineer

1 Incl
As stated

Copies furnished:
Mr. Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief
Bureau of Flood Plain Regulation
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

2

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist.	Avail and/or special
<input checked="checked" type="checkbox"/>	

VERONA LAKE DAM (NJ00386)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 14 November 1979 by Storch Engineers under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Verona Lake Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's spillway is considered inadequate because a flow equivalent to 33 percent of the Spillway Design Flood - SDF - would cause the dam to be overtopped. (The SDF, in this instance, is one half of the Probable Maximum Flood). The decision to consider the spillway "inadequate" instead of "seriously inadequate" is based on the determination that dam failure from overtopping would not significantly increase the hazard to loss of life downstream from the dam from that which would exist just before overtopping failure. To ensure adequacy of the structure, the following actions, as a minimum, are recommended:


a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.

b. With the lake drawn down, the masonry spillway should be thoroughly inspected by a professional consultant engaged by the owner within six months from the date of approval of this report. Based on the inspection, together with any necessary subsoil, seepage and structural investigations, the need for remedial measures should be determined and the measures implemented.

c. The owner should develop an emergency action plan and downstream warning system within six months from the date of approval of this report.

d. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam within one year from the date of approval of this report.

APPROVED:


JAMES G. FON
Colonel, Corps of Engineers
District Engineer

DATE: 24 Jul '80

**PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM**

Name of Dam: Verona Lake Dam, NJ00386
State Located: New Jersey
County Located: Essex
Drainage Basin: Passaic River
Stream: Peckman River
Date of Inspection: November 14, 1979

Assessment of General Condition of Dam

Based on visual inspection, past operational performance and Phase I engineering analyses, Verona Lake Dam is assessed as being in fair overall condition.

Hydraulic and hydrologic analyses indicate that the spillway is inadequate. Discharge capacity of the spillway is not sufficient to pass the designated spillway design flood (SDF) without an overtopping of the dam. (The SDF for Verona Lake Dam is equal to one-half the probable maximum flood.) The spillway is capable of passing approximately 16 percent of the probable maximum flood or 32 percent of the SDF. Therefore, the owner should engage a professional engineer experienced in the design and construction of dams in the near future to perform accurate hydraulic and hydrologic analyses relating to the spillway capacity. Based on the findings of the analyses, the need for and type of remedial measures should be determined and then implemented.

The owner should, in the near future, develop an emergency action plan together with an effective warning system outlining actions to be taken by the operator to minimize downstream effects of an emergency at the dam.

No significant signs of distress were observed in the embankment. However, evidence of leaching was observed in the lower portion of the spillway. Therefore, the spillway should be inspected with the lake drawn down by a professional engineer experienced in the design and construction of dams. Based on the inspection, together with any necessary subsoil, seepage and structural investigations, the need for remedial measures should be determined and the measures implemented.

In the near future, the owner of the dam should develop written operating procedures and a periodic maintenance plan to insure the safety of the dam.

(9) Final report
(13) DASH 61-77-C-0012

(11) F-L 18 12 (12) 241

Richard J. McDermott

(10) Richard J. McDermott, P.E.

John E. Gribbin
John E. Gribbin, P.E.

(6) National Dam Safety Program,
Verona Lake Dam (NJ00386), Passaic
River Basin, Passaic River, Essex
County, New Jersey. Phase I
Inspection Report.



OVERVIEW - VERONA LAKE DAM

29 NOVEMBER 1979

TABLE OF CONTENTS

	<u>Page</u>
ASSESSMENT OF GENERAL CONDITION OF DAM	i
OVERVIEW PHOTO	iii
TABLE OF CONTENTS	iv
PREFACE	vi
SECTION 1 - PROJECT INFORMATION	1
1.1 General	
1.2 Description of Project	
1.3 Pertinent Data	
SECTION 2 - ENGINEERING DATA	8
2.1 Design	
2.2 Construction	
2.3 Operation	
2.4 Evaluation	
SECTION 3 - VISUAL INSPECTION	10
3.1 Findings	
SECTION 4 - OPERATIONAL PROCEDURES	12
4.1 Procedures	
4.2 Maintenance of Dam	
4.3 Maintenance of Operating Facilities	
4.4 Description of Warning System	
4.5 Evaluation	

TABLE OF CONTENTS (cont.)

	<u>Page</u>
SECTION 5 - HYDRAULIC/HYDROLOGIC	13
5.1 Evaluation of Features	
SECTION 6 - STRUCTURAL STABILITY	15
6.1 Evaluation of Structural Stability	
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS	17
7.1 Dam Assessment	
7.2 Recommendations	
PLATES	
1 KEY MAP	
2 VICINITY MAP	
3 SOIL MAP	
4 GENERAL PLAN	
5 SPILLWAY SECTION	
6 PHOTO LOCATION PLAN	
APPENDICES	
1 Check List - Visual Inspection	
Check List - Engineering Data	
2 Photographs	
3 Engineering Data	
4 Hydraulic/Hydrologic Computations	
5 Bibliography	

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 30214. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that the unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**

VERONA LAKE DAM, I.D. NJ00386

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The Division of Water Resources of the New Jersey Department of Environmental Protection (NJDEP) in cooperation with the Philadelphia District of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the State of New Jersey. Storch Engineers has been retained by the NJDEP to inspect and report on a selected group of these dams. The NJDEP is under agreement with the Philadelphia District of the Corps of Engineers.

b. Purpose of Inspection

The visual inspection of Verona Lake Dam was made on November 14, 1979. The purpose of the inspection was to make a general assessment of the structural integrity and operational adequacy of the dam structure and its appurtenances.

1.2 Description of Project

a. Description of Dam and Appurtenances

Verona Lake Dam consists of a masonry overflow spillway with earth embankment abutting each end. The masonry overflow portion consists of a sloped downstream face and a concrete crest. At the junction between spillway and earth embankments, stone masonry training walls extend upstream and downstream from the spillway.

The spillway is 124 feet in length while the overall length of the dam, which is oriented approximately east/west is 438 feet. The elevation of the spillway crest is 343.9 (N.G.V.D.) while that of the dam crest is 345.9. The hydraulic height of the dam is 13 feet and structural height is estimated to be 16.3 feet. The outlet works for this dam consists of a 24-inch cast iron pipe located at the west side of the spillway. This outlet is controlled by a gate valve located in a manhole adjacent to the spillway.

b. Location

Verona Lake Dam is located in Verona Park, Borough of Verona, Essex County, New Jersey. Constructed across Peckman River, the dam impounds Verona Lake which is located within the park. The dam is readily accessible by park roads.

c. Size and Hazard Classification

Size and Hazard Classification criteria presented in "Recommended Guidelines for Safety Inspection of Dams," published by the U.S. Army Corps of Engineers are as follows:

SIZE CLASSIFICATION

	<u>Impoundment</u>	
	<u>Storage (Ac-ft)</u>	<u>Height (Ft.)</u>
Small	< 1000 and ≥ 50	< 40 and ≥ 25
Intermediate	≥ 1000 and $< 50,000$	≥ 40 and < 100
Large	$\geq 50,000$	≥ 100

HAZARD POTENTIAL CLASSIFICATION

<u>Category</u>	<u>Loss of Life</u> (Extent of Development)	<u>Economic Loss</u> (Extent of Development)
Low	None expected (no permanent structures for human habitation)	Minimal (Undeveloped to occasional structures or agriculture)
Significant	Few (No urban developments and no more than a small number of inhabitable structures)	Appreciable (Notable agriculture, industry or structures)
High	More than a small number	Excessive (Extensive community, industry or agriculture)

The following data relating to size and downstream hazard for Verona Lake Dam have been obtained for this Phase I assessment:

Storage: 96 Acre-feet

Height: 13 feet

Potential Loss of Life:

Heavily used road (Bloomfield Avenue) and urban development within downstream flood plain. Failure of dam could cause loss of life.

Potential Economic Loss:

Dam failure could cause heavy damage to the Bloomfield Avenue bridge as well as downstream development.

Therefore, Verona Lake Dam is classified as "Small" size and "High" hazard potential.

d. Ownership

Verona Lake Dam is owned and operated by Essex County Parks Division.

e. Purpose of Dam

The purpose of the dam is the impoundment of a lake used for recreation.

f. Design and Construction History

Verona Lake Dam reportedly was originally constructed in 1903 with a clay berm on the upstream side and a masonry wall on the downstream side. In 1928 a new masonry face with footing was added to the downstream side and a new concrete crest added to the entire length of the masonry overflow portion of the dam. Plans for the 1928 improvement are available in NJDEP files.

g. Normal Operational Procedures

The dam and appurtenances are operated and maintained by Essex County Parks Division. There is no fixed schedule for maintenance; repairs are made as the need arises.

1.3 Pertinent Data

a. Drainage Area 1.9 square miles

b. Discharge at Damsite

Maximum flood at damsite	Unknown
Outlet works at pool elevation	16 c.f.s.
Spillway capacity at top of dam	1076 c.f.s.

c. Elevation (Feet above MSL)

Top of dam	345.9
Maximum pool-design surcharge	347.2
Recreation pool	343.9
Spillway crest	343.9
Stream bed at centerline of dam	332.9
Maximum tailwater	339.0 (Estimated)

d. Reservoir

Length of maximum pool	2,500 feet (Estimated)
Length of recreation pool	2,400 feet (Scaled)

e. Storage (Acre-feet)

Recreation pool	60 acre-feet
Design surcharge	121 acre-feet
Top of dam	95 acre-feet

f. Reservoir Surface (Acres)

Top of dam	19.1 acres (Estimated)
Maximum pool	20.6 acres (Estimated)
Recreation pool	16.5 acres
Spillway crest	16.5 acres

g. Dam

Type	Masonry/Earthfill
Length	438 feet
Height	13 feet
Sideslopes	
Embankments-Upstream	2 horiz. to 1 vert.
-Downstream	12 horiz. to 1 vert.
Masonry -Upstream	2 horiz. to 1 vert.
-Downstream	1 horiz. to 2 vert.
Zoning	Unknown
Impervious core	Unknown
Cutoff	Unknown
Grout curtain	Unknown

h. Diversion and Regulating Tunnel N.A.

i. Spillway

Type	Uncontrolled concrete weir
Length of weir	124 feet
Crest elevation	343.9
Gates	N.A.
Approach channel	N.A.
Discharge channel	Stone paved channel

j. Regulating Outlet

24-inch gated CIP outlet

SECTION 2: ENGINEERING DATA

2.1 Design

Plans of improvements completed in 1928 by Essex County Park Commission are available in the NJDEP files. Hydraulic calculations prepared by the State of New Jersey in 1934 indicated that the spillway capacity was adequate for the applicable design flood. (The choice of design flood was unclear.) No design drawings relating to the original construction in 1903 are available.

2.2 Construction

Inspection reports indicating that the 1928 improvements were completed satisfactorily are available in the NJDEP files. No drawings or inspection reports relating to the original construction are available.

2.3 Operation

No records of operation and maintenance of the dam subsequent to construction are available. An inspection report written in 1968 for the State of New Jersey indicated that the dam structure was in stable condition.

2.4 Evaluation

a. Availability

Available engineering information is limited to that which is on file at the NJDEP. This file contains information relating to the reconstruction work done in 1928. No information pertaining to the original construction is available.

b. Adequacy

Available engineering data pertaining to Verona Lake Dam provided limited assistance in performing this Phase I evaluation. A list of absent information is included in Paragraph 7.1.b.

c. Validity

In general, information that could be verified was found to be valid within a reasonable allowance for error. However, one minor discrepancy was noted: whereas the plans and calculations indicated a two staged spillway with a lower section, or notch, in the center, field inspection revealed a spillway crest with a depression in the center.

SECTION 3: VISUAL INSPECTION

3.1 Findings

a. General

The inspection of Verona Lake Dam took place on November 14, 1979 by members of the staff of Storch Engineers. A copy of the visual inspection check list is contained in Appendix 1. The following procedures were employed for the inspection:

- 1) The embankment of the dam, appurtenant structures and adjacent areas were examined.
- 2) The embankment and appurtenant structures were measured and key elevations determined by a surveyor's level.
- 3) The embankment and appurtenant structures and adjacent areas were photographed.
- 4) Depths of water were measured at various locations in the lake.

b. Spillway

The masonry overflow portion of the dam comprises the spillway. The crest of the spillway is formed with a depressed section at the center where most dry weather overflow occurs. Several areas of leaching were observed on the downstream face near the toe of the spillway. Some leachate did not appear to be composed of soil, but appeared to contain deteriorated mortar. Evidence of leakage was observed

discharging immediately below the concrete cap which forms the spillway crest. The stone masonry training walls appeared to be in good condition with small amounts of patching near the top.

The outlet works control mechanism and the manhole housing it appeared to be in satisfactory condition. The discharge end of the 24-inch cast iron outlet pipe appeared to be clear and in satisfactory condition.

c. Embankments

Both embankments are grass covered with paved walkways on their crests. The upstream face of the west embankment consists of a continuation of the west training wall of the spillway. There are no visible signs of erosion or other distress in the embankments.

d. Reservoir Area

Verona Lake has a maximum length of about 2400 feet with widths varying from 160 to 480 feet. The entire shore line and most of the watershed constitutes a County park.

e. Downstream Channel

Discharge from Verona Lake Dam enters Peckman River by way of a rectangular channel paved with cobble stones. Two pedestrian bridges span the channel about 40 feet and 140 feet downstream from the spillway. Further downstream, the channel passes under a concrete road bridge into a natural channel through an urban area of Verona. Buildings near the channel are estimated to be 7 to 10 feet above the stream bed.

SECTION 4: OPERATIONAL PROCEDURES

4.1 Procedures

The water level in Verona Lake is naturally controlled by overflow over the spillway. Reportedly the lake is not lowered for any purpose. Although the gate was not opened at the time of inspection, the operating mechanism appeared to be in satisfactory condition.

4.2 Maintenance of the Dam

There is no program of regular inspection and maintenance of the dam and appurtenant structures. Maintenance is performed by the staff of Essex County Park Division on an "as needed" basis.

4.3 Maintenance of Operating Facilities

Maintenance of operating facilities is performed on an "as needed" basis.

4.4 Description of Warning System

Reportedly, no formal warning system is in use at the present time. However, surveillance is performed by the Essex County Division of Parks.

4.5 Evaluation of Operational Adequacy

The operation of the dam has been satisfactory in that no overtopping has been recorded.

Maintenance documentation is poor but the overall condition of the dam indicates that normal maintenance has been generally satisfactory.

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. Design Data

The quantity of storm water runoff that the spillway should be able to pass without an overtopping of the dam is based on the size and hazard classification of the dam. This runoff, called the Spillway Design Flood (SDF), is described in terms of frequency or probable maximum flood (PMF) depending on the extent of the dam's size and potential hazard. According to the "Recommended Guidelines for Safety Inspection of Dams," published by the U.S. Army Corps of Engineers, the SDF for Verona Lake Dam falls in a range of 1/2 PMF to PMF. In this case the low end of the range, 1/2 PMF, is chosen since the factors used to select size classification are on the low side of their respective ranges.

The SDF hydrograph for Verona Lake was computed by use of the HEC-1-DB computer program using the SCS Method. Hydrologic computations and computer output are contained in Appendix 4. The calculated SDF peak inflow for Verona Lake Dam is 3577 c.f.s.

Discharge capacity for the spillway was computed by considering free discharge over the masonry portion of the dam. Hydraulic computations are contained in Appendix 4.

The SDF was routed through the dam by the use of the HEC-1-DB computer program using the modified Puls method. In routing the SDF, it was found that the dam would be overtopped to a height of 1.3 feet. A dam breach would probably not significantly increase the hazard potential for

loss of life downstream due to dam failure from overtopping over that which exists without failure. Accordingly, the subject spillway is assessed as being inadequate in accordance with criteria developed by the U.S. Army Corps of Engineers.

b. Experience Data

No record has indicated that the dam has ever been overtopped.

c. Visual observation

No evidence was found at the time of inspection that would indicate that the dam had been overtopped.

d. Overtopping Potential

As indicated in paragraph 5.1.a, a storm of magnitude equivalent to the SDF would cause overtopping of the dam by a height of 1.3 above the top of the dam. The spillway is capable of passing approximately 16% of the PMF or 32% of the SDF with lake level equal to the top of the dam (elev. 345.9).

e. Drawdown Time

Drawdown of the lake is accomplished by opening the gate in the 24-inch cast iron outlet pipe. Total time for drawdown is estimated to be 3.7 days. (See Appendix 4)

SECTION 6: STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

The embankment appeared, at the time of inspection, to be outwardly stable. No significant indications of possible distress were observed. Approximately 2 feet above normal tailwater elevation, some leaching was observed at the spillway. An accurate determination of the severity of the leaching cannot be made without further investigation beyond the scope of a Phase I inspection.

b. Generalized Soils Description

The generalized soils description of the dam site consists of silty-loams and sandy-silts with varying amounts of pebbles, gravel and boulders intermingled with silty sands, silty gravels, sandy gravels and gravelly sands. These materials overlay bedrock composed of fine grained trap rock at depths of 10 to 20 feet or greater.

c. Design and Construction Data

Analyses of structural stability and construction data for the embankment and spillway structure are not available.

d. Operating Records

No operating records are available for the dam. Reports of inspections made by the State of New Jersey in 1928 and 1968 are contained in the files of NJDEP. The dam was in good condition according to these reports.

e. Post Construction Changes

Records on file at the NJDEP indicate that the dam was originally constructed in 1903 as a stonewall-earth dam. In 1928, improvements were made to the dam by construction of a concrete retaining wall on the downstream side of the dam. A concrete cap was also built along the crest of the dam. The entire length of the dam became an overflow spillway. The original spillway was filled by clay to form the same slope as the embankment. The original section of the clay embankment was undisturbed. Six inches of concrete base overlaid with grouted stone pavement was constructed to cover the bed and sides of the downstream channel for a distance of approximately 1000 feet.

f. Seismic Stability

Verona Lake Dam is located in Seismic Zone 1 as defined in "Recommended Guideline for Safety Inspection of Dams," which is a zone of very low seismic activity. Experience indicates that dams in Seismic Zone 1 will have adequate stability under seismic loading conditions if they have adequate stability under static loading conditions. Verona Lake Dam appeared to be outwardly stable under static loading conditions.

SECTION 7: ASSESSMENT AND RECOMMENDATIONS

7.1 Dam Assessment

a. Safety

Based on hydraulic and hydrologic analyses outlined in Section 5 and Appendix 4, the spillway of Verona Lake Dam is assessed as being inadequate. The spillway is not able to pass the SDF without an overtopping of the dam.

The dam appeared to be outwardly stable at the time of inspection. The observed leaching is not considered to be an immediate indication of instability. However, sufficient data is not available to allow a complete assessment of the present structural condition of the dam and appurtenances.

b. Adequacy of Information

Information sources for this study include 1) field inspection, 2) USGS quadrangle sheet, 3) aerial photography from Essex County, 4) plans, inspection reports and correspondence in the NJDEP file, and 5) consultation with maintenance and operation personnel of Essex County Division of Parks.

The information obtained is sufficient to allow a Phase I assessment as outlined in "Recommended Guidelines for Safety Inspection of Dams."

Some data not available are as follows:

1. Description of dam embankment structures and material.
2. Original construction records.
3. Soils Report.
4. Hydraulic and structural design reports.

c. Necessity for Additional Data/Evaluation

Additional evaluation is considered necessary in order to assess the structural stability of the dam.

7.2 Recommendations

a. Remedial Measures

Based on hydraulic and hydrologic analyses outlined in paragraph 5.1.a, the spillway is considered to be inadequate. Therefore, it is recommended that a professional engineer experienced in the design and construction of dams be engaged in the near future to perform more accurate hydraulic and hydrologic analyses relating to the spillway capacity. Based on the findings of these analyses, the need for and type of remedial measures should be determined and then implemented.


The owner should, in the near future, develop an emergency action plan together with an effective warning system outlining actions to be taken by the operator to minimize downstream effects of an emergency at the dam.

In addition, it is recommended that the following remedial measures be undertaken by the owner in the near future. With the lake drawn down, the masonry spillway should be thoroughly inspected by a professional engineer experienced in the design and construction of dams. Based on the inspection, together with any necessary subsoil, seepage and structural investigations, the need for remedial measures should be determined and the measures implemented.

b. Maintenance

In the near future, the owner of the dam should develop written operating procedures and a periodic maintenance plan to insure the safety of the dam.

PLATES






PLATE 2

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS


VICINITY MAP

VERONA LAKE DAM

I.D. N.J. 00386

SCALE: AS SHOWN

DATE: NOV., 1979



Legend

- GM-42 Silty-loams and sandy-silts with varying amounts of pebbles, gravel and boulders.
- GS-12 Silty sands, silty gravels, sandy gravels and gravelly sands.

NOTE: Information taken from Rutgers University Soil Survey of New Jersey, Report No. 2, Essex County, and Geologic Map of New Jersey prepared by Lewis and Kummel.

PLATE 3

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY


DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS SOIL MAP VERONA LAKE DAM

I.D. NJ00386

SCALE: NONE

DATE: NOV, 1979



NOTE:

Information taken from plan
"Proposed Verona Lake Dam
of the Essex County Park
Commission" and field
inspection. Nov. 14 1979





PLATE 4

STORCH ENGINEERS FLORHAM PARK, NEW JERSEY	DIVISION OF WATER RESOURCES N.J. DEPT. OF ENVIR. PROTECTION TRENTON, NEW JERSEY
INSPECTION AND EVALUATION OF DAMS GENERAL PLAN VERONA LAKE DAM	
I.D.N.J. 00386	SCALE: NOT TO SCALE
	DATE: DEC., 1979



NOTES:

1. Information taken from plan
 "Proposed Verona Lake Dam
 of the Essex County Park
 Commission" and field
 inspection Nov. 14, 1979

2 Elevations based on NGVD. taken from Essex Co Park




PLATE 5

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY


INSPECTION AND EVALUATION OF DAMS
SPILLWAY SECTION
VERONA LAKE DAM

I.D.N.J. 00386

SCALE: NOT TO SCALE

DATE: DEC. 1979

2






PLATE 6

STORCH ENGINEERS FLORHAM PARK, NEW JERSEY	DIVISION OF WATER RESOURCES N.J. DEPT. OF ENVIR. PROTECTION TRENTON, NEW JERSEY
INSPECTION AND EVALUATION OF DAMS PHOTO LOCATION PLAN VERONA LAKE DAM	
I.D. N.J. 00386	SCALE NOT TO SCALE
	DATE DEC., 1979

2

APPENDIX 1

Check List - Visual Inspection

Check List - Engineering Data

Check List
Visual Inspection
Phase I

Name of Dam Verona Lake Dam County Essex State New Jersey Coordinators NJDEP

Date(s) Inspection 11/14/79 Weather P-Cloudy Temperature 50°F

Pool Elevation at Time of Inspection 343.6 M.S.L. Tailwater at Time of Inspection 333.5 M.S.L.

Inspection Personnel:

John Gribbin Alan Volle

Ronald Lai Thomas Miller

Richard McDermott

J. Gribbin Recorder

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
GENERAL	Stone masonry overflow appeared structurally stable. Some leaching was observed near the toe.	
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Junction at both ends of masonry overflow section appeared sound.	
DRAINS	None	
WATER PASSAGES	None	
APRON	Masonry apron and stilling basin appeared to be in satisfactory condition.	
VERTICAL AND HORIZONTAL ALIGNMENT	Horizontal alignment appeared to be straight. Vertical alignment of crest slightly depressed at the center.	

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	No major cracks were observed. Several slight surface cracks were evident along the crest of spillway.	Recommend renovation of spillway crest.
STRUCTURAL CRACKING	None observed.	
CONSTRUCTION JOINTS	No distress observed.	
MONOLITH JOINTS	N.A.	
LEAKAGE	Leakage observed immediately below crest of masonry dam.	
SEEPAGE	Evidence of leaching was observed at the base of spillway. May be due to leakage or seepage.	Recommend further investigation.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
GENERAL	Paved walkway on crest appeared to be in satisfactory condition. Embankment generally grassed with some trees.	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Appeared stable.	
ANY NOTICEABLE SEEPAGE	None observed.	
STAFF GAGE AND RECORDER	None	
DRAINS	Weep holes at base of stone masonry training walls.	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None observed.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE.	None observed.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None observed.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Alignment of crest appeared irregular.	Embankments appeared to be graded and landscaped as part of park in which dam is located.
RIPRAP FAILURES	None observed.	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SURFACES IN OUTLET CONDUIT	N.A.	
INTAKE STRUCTURE	Intake submerged and could not be observed during inspection.	
OUTLET STRUCTURE	Outlet of 24" cast iron pipe appeared to be clear and in satisfactory condition.	
OUTLET CHANNEL	Same as spillway discharge channel.	
GATE AND GATE HOUSING	Manhole for gate valve control and control mechanism appeared to be in satisfactory condition.	Outlet control not operated at time of inspection.

SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Conc. weir joined by cap constructed in 1928 on top of original stone masonry structure. Appeared to be in fair condition with several transverse surface cracks.	Recommend renovation of spillway crest.
APPROACH CHANNEL	N.A.	
DISCHARGE CHANNEL	Spillway discharges into paved discharge channel. Stone masonry walls and bottom appeared to be in satisfactory condition.	

INSTRUMENTATION

VISUAL EXAMINATION	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None	
OBSERVATION WELLS	None	
WEIRS	None	
PIEZOMETERS	None	
OTHER		

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Shore slopes have average pitch of approx. 5%.	
SEDIMENTATION	Sounding in the vicinity of spillway indicate silt deposit approx. 4 feet thick.	
STRUCTURES ALONG BANKS	One pedestrian bridge located on lake.	

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	No obstruction or debris were observed in downstream channel.	Channel consists of conc. and masonry lined channel for approx. 1000 feet in park.
SLOPES	Vertical side slopes on stone masonry walls.	
STRUCTURES ALONG BANKS	No building along channel for 1000 feet downstream. Two concrete bridges for pedestrians and park vehicles located along channel within park. Concrete road bridge located 1000 feet downstream. Urban development include buildings along banks downstream from bridge in flood plain of dam.	

**CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION**

ITEM	REMARKS
DAM - PLAN	Available in NJDEP file entitled " General Plan Proposed Verona Lake" by Essex County Park Commission.
SECTIONS	
SPILLWAY - PLAN	See above.
SECTIONS	
DETAILS	
OPERATING EQUIPMENT PLANS & DETAILS	Not Available.
OUTLETS - PLAN	Available in above plans.
DETAILS	Not Available.
CONSTRAINTS	Not Available.
DISCHARGE RATINGS	Not Available.
HYDRAULIC/HYDROLOGIC DATA	
RAINFALL/RESERVOIR RECORDS	Not Available.
CONSTRUCTION HISTORY	Information available on addition of downstream face in 1928 in NJDEP.
LOCATION MAP	Not Available.

ITEM	REMARKS
DESIGN REPORTS	Not Available
GEOLOGY REPORTS	Not Available
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	Not Available
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	Not Available
POST-CONSTRUCTION SURVEYS OF DAM	Not Available
BORROW SOURCES	Not Available

ITEM	REMARKS
------	---------

MONITORING SYSTEMS	None
--------------------	------

Additions of downstream face in 1928.

MODIFICATIONS	
---------------	--

HIGH POOL RECORDS	None
-------------------	------

POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	One inspection report done in 1968 is available in NJDEP file.
---	--

PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	Records not available.
---	------------------------

MAINTENANCE OPERATION RECORDS	Not available.
-------------------------------	----------------

APPENDIX 2

Photographs



PHOTO 1
SPILLWAY




PHOTO 2
CONCRETE BRIDGE AND STONE WEIR DOWNSTREAM FROM DAM

VERONA LAKE DAM
14 NOVEMBER 1979



PHOTO 3

LEAKAGE AT CREST OF SPILLWAY




PHOTO 4

LEACHATE NEAR TOE OF SPILLWAY

VERONA LAKE DAM
14 NOVEMBER 1979



PHOTO 5

CREST AND DOWNSTREAM FACE OF SPILLWAY



PHOTO 6

CRACK IN CREST OF SPILLWAY NEAR CENTER

VERONA LAKE DAM
14 NOVEMBER 1979



PHOTO 7

UPSTREAM FACE OF EAST EMBANKMENT



PHOTO 8

DOWNSTREAM FACE OF EAST EMBANKMENT

VERONA LAKE DAM
14 NOVEMBER 1979



PHOTO 9

29 NOVEMBER 1979

DOWNSTREAM CHANNEL



PHOTO 10

14 NOVEMBER 1979

ROAD BRIDGE DOWNSTREAM FROM DAM

VERONA LAKE DAM

APPENDIX 3

Engineering Data

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: Urban and Wooded

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 343.9 (60 Acre-feet)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): N.A.

ELEVATION MAXIMUM DESIGN POOL: 347.2

ELEVATION TOP DAM: 345.9

SPILLWAY CREST: Straight Masonry Weir

- a. Elevation 343.6 to 343.9
- b. Type Irregular Section
- c. Width 7.5 feet
- d. Length 124 feet
- e. Location Spillover Center of dam
- f. Number and Type of Gates None

OUTLET WORKS: 24-inch cast iron pipe with gate valve

- a. Type Outlet pipe with gate valve
- b. Location N/W end of dam
- c. Entrance inverts 333.6
- d. Exit inverts 332.7
- e. Emergency draindown facilities: Gate-valve

HYDROMETEOROLOGICAL GAGES: None

- a. Type N.A.
- b. Location N.A.
- c. Records N.A.

MAXIMUM NON-DAMAGING DISCHARGE:

(Lake stage equal to top of dam) 1076 c.f.s.
(Elev. 345.9)

APPENDIX 4

Hydraulic/Hydrologic Computations

Project Vernon Lake Dam
S.E. 1132 CMade By RL Date 12-21-79
Chkd By JG Date 1/4/80HydrologyHydrologic Analysis

Runoff hydrograph will be developed by
HEC-1-DB using triangular hydrograph
with the curvilinear transformation.

Drainage Area = 1.9 Sq. miles

Infiltration Data

Initial infiltration
Constant "

1.0 in
0.1 in/hr.

Time of Concentration

By chart on SCS TR-55 overland flow

Overland flow 5,000 ft 5%

Channel flow 5,500 ft 1%

$$T_c = \left(\frac{5000}{1.6} + \frac{5500}{1.5} \right) \frac{1}{3600}$$

$$\doteq \underline{\underline{1.9 \text{ hour}}}$$

Project Verona Lake Dam Made By RL Date 3-3-80
S.E. 1132C Chkd By JG Date 3/4/80Time of Concentration

Nomograph "Design of Small Dams"

$$L = 10500 \text{ ft} \approx 2 \text{ mi}$$

$$H = 305$$

$$\begin{aligned} T &= \left(\frac{11.9 L^3}{H} \right)^{0.385} \\ &= \left[\frac{11.9 (2)^3}{305} \right]^{0.385} \\ &= \underline{\underline{0.64 \text{ hr.}}} \end{aligned}$$

Time of Concentration

Snyder's lag

$$t = C_t (L L_{ca})^{0.3}$$

 $t = \text{lag time (hr.)}$

$$C_t = 2.0$$

 $L = \text{length of the main stream channel (mi) from the outlet to the divide}$
 $L_{ca} = \text{length along the main channel to a point opposite the watershed centroid (mi)}$

$$\begin{aligned} t &= 2[(2)(1.1)]^{0.3} \\ &= \underline{\underline{2.5 \text{ hr.}}} \end{aligned}$$

Project Verona Lake DamMade By RL Date 12-21-79S.E. 1132CChkd By JG Date 1/4/80Time of Concentration

By Kerby

Pg 14-36
"Handbook of Applied
Hydrology" Chow
McGraw Hill

$$t_c^{2.14} = \frac{2}{3} \frac{Ln}{\sqrt{s}}$$

 t_c = time of concentration
in minutes L = Length of overland
flow in ft. s = slope n = 0.4 roughness
coef.

$$t_c^{2.14} = \frac{2}{3} \frac{5000 (0.4)}{\sqrt{0.05}}$$

$$t_c = 0.97 \text{ hr.}$$


$$\text{Channel flow} = 1 \text{ hr}$$

$$\text{total } T_c = 1.97 \text{ hr.}$$

Use 1.9 as T_c

$$\text{and } 1.9 \times 0.6 = \underline{\underline{1.14}} \text{ for Lag}$$

STORCH ENGINEERS

Sheet 4 of 8Project Verona Lake DamMade By RL Date 12-21-79S.E. 1132 CChkd By JG Date 1/4/80

$$Q = CLH^{3/2} \quad C = 3.1$$


Ref. 5-44 "Handbook of Hydraulics
King et al."

Length of Spillway = 124 feet

Stage Discharge Tabulation

W.L. (ft)	Head H (ft)	$H^{3/2}$	C	Q (cfs)
343.9	0	0	3.1	0
344.9	1	1	3.1	384
345.9	2	2.8	3.1	1076
346.9	3	5.2	3.1	1999
347.9	4	8.0	3.1	3075
348.9	5	11.2	3.1	4305

STORCH ENGINEERS

Sheet 5 of 8Project Verona Lake DamMade By RL Date 12-21-79S.E. 1132 CChkd By JG Date 1/4/80SPILLWAYSTAGE DISCHARGE CURVE

STORCH ENGINEERS

Sheet 6 of 8

Project Verona Lake Dam

Made By RL Date 12-26-79

Chkd By JG Date 1/4/80

Lake Storage Volume

Elev. (M.S.L.)	Surface Area (Ac)
333.6	0
343.6	16.5
360.0	35.0
380.0	112.0

HEC-1-DB program will develop storage capacity from surface area and elev.

Project Verona Lake DamMade By RL Date 12-21-79S.E. 1132 CChkd By JG Date 1/4/80Outlet Works Capacity

24" CIP inlet at 333.6
outlet at 332.7

Approximately 90' of 24" CIP
slope of pipe = 1%

Outlet control "Hydraulic charts for
The selection of Highway Culverts"
Bureau of Public Roads

For HW = 343.6

TW = 332.7

H = 10.9

Q = 16 cfs


Time required for total drawdown

$$= \frac{\text{Total storage}}{\text{rate of drawdown}} \quad \text{Assume inflow} = 0$$

$$= \frac{59 \times 43560}{8 \times 3600} \quad \text{hrs}$$

$$= \underline{\underline{89}} \quad \text{hrs}$$

$$\div \underline{\underline{3.7}} \quad \text{days}$$

Project Verona Lake DamMade By RL Date _____1132cChkd By JG Date 1/4/80Overtopping Potential

HEC-1-DB COMPUTATIONS

123 1 1 1 2 1 145 AESSD
AABBJJX.XYPTJXKXYYYSSSSXAAAAA

2005
11
0.50
1
-1.01
343.90
333.60
343.99
345.99

5
0.4
LAKE
25.7
1.14
-0.05
DAM
344.9
384
16.5
343.6
2.63

1	0.3	INFL	2.0	ROUT	345.9	1076	35	1.5
		100				360		

0.2	HYDRO	109	ISCHA	346.9	314
			1	1999	
				112	
				380	

0.1
PH TO
1.9
117
THRU
1
347.9
3075

RONA (

M

348.9
4305

3 1 1.0 1 343.6

0.1 -1

3 4

**RUN DATE# 79/12/28:
TIME# 10.04.53:**

**NATIONAL DAM SAFETY PROGRAM
VERONA LAKE DAM NEW JERSEY
MULTI RATIO ROUTING**

NO	NMR	NMIN	TDAY	JOB SPECIFICATION				IPRI	NSTAN
200	0	5	0	IMR	IMIN	METRG	IPRI	0	
			JOBEN	NMT	LROPT	TRACE			
			5	0	0	0			

```

RTIOS=      .50
          .40      .30      .20      .10
MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 5 LRTIO= 1

```

```

*****
SUB-AREA RUNOFF COMPUTATION
*****
INFLW HYDROGRAPH TO VERONA LAKE
*****
IHAQ ICOMP IECON ITAPE JPLY JPRT INAME ISTAGE IAU0
LAKE 0 0 0 0 0 0 0 0 0 0
IHYD IUNG TAREA SNAP HYDROGRAPH DATA
1 2 1.90 0.00 TRSDA TRSPC
RATIO ISNOW ISAME LOCAL
0.000 0 1 0
PRECIP DATA
R6 R12 R24 P48 R72 R96
PMS 25.70 100.00 109.00 117.00 0.00 0.00
SPEE 0.00
IS .60
*****
TRSPC COMPUTED BY THE PROGRAM

```

[illegible]

NO.OA	MR.MN	PERIOD	RAIN	EXCS	LOSS	COMP
01	05	1	01	00	01	2.
01	10	2	01	00	01	2.
01	15	3	01	00	01	2.
01	20	4	01	00	01	1.
01	25	5	01	00	01	1.
01	30	6	01	00	01	1.
01	35	7	01	00	01	1.
01	40	8	01	00	01	1.
01	45	9	01	00	01	1.
01	50	10	01	00	01	1.
01	55	11	01	00	01	1.
01	60	12	01	00	01	1.
01	65	13	01	00	01	1.
01	70	14	01	00	01	1.
01	75	15	01	00	01	1.
01	80	16	01	00	01	1.
01	85	17	01	00	01	1.
01	90	18	01	00	01	1.
01	95	19	01	00	01	1.
01	00	20	01	00	01	0.
01	05	21	01	00	01	0.
01	10	22	01	00	01	0.
01	15	23	01	00	01	0.
01	20	24	01	00	01	0.
01	25	25	01	00	01	0.
01	30	26	01	00	01	0.
01	35	27	01	00	01	0.
01	40	28	01	00	01	0.
01	45	29	01	00	01	0.
01	50	30	01	00	01	0.
01	55	31	01	00	01	0.
01	60	32	01	00	01	0.
01	65	33	01	00	01	0.
01	70	34	01	00	01	0.
01	75	35	01	00	01	0.
01	80	36	01	00	01	0.
01	85	37	01	00	01	0.
01	90	38	01	00	01	0.
01	95	39	01	00	01	0.
01	00	40	01	00	01	0.
01	05	41	01	00	01	0.
01	10	42	01	00	01	0.
01	15	43	01	00	01	0.
01	20	44	01	00	01	0.
01	25	45	01	00	01	0.
01	30	46	01	00	01	0.
01	35	47	01	00	01	0.
01	40	48	01	00	01	0.
01	45	49	01	00	01	0.
01	50	50	01	00	01	0.
01	55	51	01	00	01	0.
01	60	52	01	00	01	0.
01	65	53	01	00	01	0.
01	70	54	01	00	01	0.
01	75	55	01	00	01	0.
01	80	56	01	00	01	0.
01	85	57	01	00	01	0.
01	90	58	01	00	01	0.
01	95	59	01	00	01	0.
01	00	60	01	00	01	0.
01	05	61	01	00	01	0.
01	10	62	01	00	01	0.
01	15	63	01	00	01	0.
01	20	64	01	00	01	0.
01	25	65	01	00	01	0.
01	30	66	01	00	01	0.
01	35	67	01	00	01	0.
01	40	68	01	00	01	0.
01	45	69	01	00	01	0.
01	50	70	01	00	01	0.
01	55	71	01	00	01	0.
01	60	72	01	00	01	0.

MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
-------	-------	--------	------	------	------	--------

1	10	10	10	10	10	10
2	10	10	10	10	10	10
3	10	10	10	10	10	10
4	10	10	10	10	10	10
5	10	10	10	10	10	10
6	10	10	10	10	10	10
7	10	10	10	10	10	10
8	10	10	10	10	10	10
9	10	10	10	10	10	10
10	10	10	10	10	10	10
11	10	10	10	10	10	10
12	10	10	10	10	10	10
13	10	10	10	10	10	10
14	10	10	10	10	10	10
15	10	10	10	10	10	10
16	10	10	10	10	10	10
17	10	10	10	10	10	10
18	10	10	10	10	10	10
19	10	10	10	10	10	10
20	10	10	10	10	10	10
21	10	10	10	10	10	10
22	10	10	10	10	10	10
23	10	10	10	10	10	10
24	10	10	10	10	10	10
25	10	10	10	10	10	10
26	10	10	10	10	10	10
27	10	10	10	10	10	10
28	10	10	10	10	10	10
29	10	10	10	10	10	10
30	10	10	10	10	10	10
31	10	10	10	10	10	10
32	10	10	10	10	10	10
33	10	10	10	10	10	10
34	10	10	10	10	10	10
35	10	10	10	10	10	10
36	10	10	10	10	10	10
37	10	10	10	10	10	10
38	10	10	10	10	10	10
39	10	10	10	10	10	10
40	10	10	10	10	10	10
41	10	10	10	10	10	10
42	10	10	10	10	10	10
43	10	10	10	10	10	10
44	10	10	10	10	10	10
45	10	10	10	10	10	10
46	10	10	10	10	10	10
47	10	10	10	10	10	10
48	10	10	10	10	10	10
49	10	10	10	10	10	10
50	10	10	10	10	10	10
51	10	10	10	10	10	10
52	10	10	10	10	10	10
53	10	10	10	10	10	10
54	10	10	10	10	10	10
55	10	10	10	10	10	10
56	10	10	10	10	10	10
57	10	10	10	10	10	10
58	10	10	10	10	10	10
59	10	10	10	10	10	10
60	10	10	10	10	10	10
61	10	10	10	10	10	10
62	10	10	10	10	10	10
63	10	10	10	10	10	10
64	10	10	10	10	10	10
65	10	10	10	10	10	10
66	10	10	10	10	10	10
67	10	10	10	10	10	10
68	10	10	10	10	10	10
69	10	10	10	10	10	10
70	10	10	10	10	10	10
71	10	10	10	10	10	10
72	10	10	10	10	10	10
73	10	10	10	10	10	10
74	10	10	10	10	10	10
75	10	10	10	10	10	10
76	10	10	10	10	10	10
77	10	10	10	10	10	10
78	10	10	10	10	10	10
79	10	10	10	10	10	10
80	10	10	10	10	10	10
81	10	10	10	10	10	10
82	10	10	10	10	10	10
83	10	10	10	10	10	10
84	10	10	10	10	10	10
85	10	10	10	10	10	10
86	10	10	10	10	10	10
87	10	10	10	10	10	10
88	10	10	10	10	10	10
89	10	10	10	10	10	10
90	10	10	10	10	10	10
91	10	10	10	10	10	10
92	10	10	10	10	10	10
93	10	10	10	10	10	10
94	10	10	10	10	10	10
95	10	10	10	10	10	10
96	10	10	10	10	10	10
97	10	10	10	10	10	10
98	10	10	10	10	10	10
99	10	10	10	10	10	10
100	10	10	10	10	10	10

MO.DA	HR.MN	PERIOD	RAIN	ENCS	LOSS	COPP Q
-------	-------	--------	------	------	------	--------

1.01	12.05	145	.17	.16	.01	257.
1.01	12.10	146	.17	.16	.01	264.
1.01	12.15	147	.17	.16	.01	277.
1.01	12.20	148	.17	.16	.01	286.
1.01	12.25	149	.17	.16	.01	300.
1.01	12.30	150	.17	.16	.01	316.
1.01	12.35	151	.17	.16	.01	416.
1.01	12.40	152	.17	.16	.01	443.
1.01	12.45	153	.17	.16	.01	564.
1.01	12.50	154	.17	.16	.01	588.
1.01	12.55	155	.17	.16	.01	600.
1.01	13.00	156	.17	.16	.01	669.
1.01	13.05	157	.21	.20	.01	681.
1.01	13.10	158	.21	.20	.01	755.
1.01	13.15	159	.21	.20	.01	1121.
1.01	13.20	160	.21	.20	.01	1225.
1.01	13.25	161	.21	.20	.01	1427.
1.01	13.30	162	.21	.20	.01	1446.
1.01	13.35	163	.21	.20	.01	1616.
1.01	13.40	164	.21	.20	.01	1755.
1.01	13.45	165	.21	.20	.01	1843.
1.01	13.50	166	.21	.20	.01	1945.
1.01	13.55	167	.21	.20	.01	2220.
1.01	14.00	168	.21	.20	.01	2271.
1.01	14.05	169	.26	.25	.01	2282.
1.01	14.10	170	.26	.25	.01	2333.
1.01	14.15	171	.26	.25	.01	2371.
1.01	14.20	172	.26	.25	.01	2377.
1.01	14.25	173	.26	.25	.01	2551.
1.01	14.30	174	.26	.25	.01	2566.
1.01	14.35	175	.26	.25	.01	2666.
1.01	14.40	176	.26	.25	.01	2666.
1.01	14.45	177	.26	.25	.01	2777.
1.01	14.50	178	.26	.25	.01	2777.
1.01	14.55	179	.26	.25	.01	2888.
1.01	15.00	180	.26	.25	.01	2888.
1.01	15.05	181	.15	.15	.01	2937.
1.01	15.10	182	.31	.30	.01	2937.
1.01	15.15	183	.31	.30	.01	3037.
1.01	15.20	184	.47	.46	.01	3037.
1.01	15.25	185	.55	.54	.01	3037.
1.01	15.30	186	1.33	.52	.01	3037.
1.01	15.35	187	2.19	.18	.01	3037.
1.01	15.40	188	.86	.85	.01	3037.
1.01	15.45	189	.55	.54	.01	3037.
1.01	15.50	190	.47	.46	.01	4477.
1.01	15.55	191	.31	.30	.01	4477.
1.01	16.00	192	.31	.30	.01	4477.
1.01	16.05	193	.24	.23	.01	5511.
1.01	16.10	194	.24	.23	.01	5566.
1.01	16.15	195	.24	.23	.01	5566.
1.01	16.20	196	.24	.23	.01	6677.
1.01	16.25	197	.24	.23	.01	6677.
1.01	16.30	198	.24	.23	.01	6677.
1.01	16.35	199	.24	.23	.01	7777.
1.01	16.40	200	.24	.23	.01	7777.
0.00	0.00	201	.24	.23	.01	7777.
0.00	0.00	202	.24	.23	.01	7777.
0.00	0.00	203	.24	.23	.01	6677.
0.00	0.00	204	.24	.23	.01	6677.
0.00	0.00	205	.19	.18	.01	6677.
0.00	0.00	206	.19	.18	.01	6677.
0.00	0.00	207	.19	.18	.01	6677.
0.00	0.00	208	.19	.18	.01	6677.
0.00	0.00	209	.19	.18	.01	6677.
0.00	0.00	210	.19	.18	.01	6677.
0.00	0.00	211	.19	.18	.01	6677.
0.00	0.00	212	.19	.18	.01	4477.
0.00	0.00	213	.19	.18	.01	4477.
0.00	0.00	214	.19	.18	.01	4477.
0.00	0.00	215	.19	.18	.01	4477.
0.00	0.00	216	.19	.18	.01	4477.

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COPP Q
00.00	00.00	217	.01	.01	.01	3972.
00.00	00.00	218	.01	.01	.01	3937.
00.00	00.00	219	.01	.01	.01	3701.
00.00	00.00	220	.01	.01	.01	3564.
00.00	00.00	221	.01	.01	.01	3431.
00.00	00.00	222	.01	.01	.01	3293.
00.00	00.00	223	.01	.01	.01	3147.
00.00	00.00	224	.01	.01	.01	2992.
00.00	00.00	225	.01	.01	.01	2826.
00.00	00.00	226	.01	.01	.01	2653.
00.00	00.00	227	.01	.01	.01	2477.
00.00	00.00	228	.01	.01	.01	2299.
00.00	00.00	229	.01	.01	.01	2123.
00.00	00.00	230	.01	.01	.01	1951.
00.00	00.00	231	.01	.01	.01	1782.
00.00	00.00	232	.01	.01	.01	1621.
00.00	00.00	233	.01	.01	.01	1469.
00.00	00.00	234	.01	.01	.01	1325.
00.00	00.00	235	.01	.01	.01	1192.
00.00	00.00	236	.01	.01	.01	1069.
00.00	00.00	237	.01	.01	.01	957.
00.00	00.00	238	.01	.01	.01	858.
00.00	00.00	239	.01	.01	.01	771.
00.00	00.00	240	.01	.01	.01	696.
00.00	00.00	241	.01	.01	.01	629.
00.00	00.00	242	.01	.01	.01	570.
00.00	00.00	243	.01	.01	.01	517.
00.00	00.00	244	.01	.01	.01	471.
00.00	00.00	245	.01	.01	.01	424.
00.00	00.00	246	.01	.01	.01	391.
00.00	00.00	247	.01	.01	.01	357.
00.00	00.00	248	.01	.01	.01	333.
00.00	00.00	249	.01	.01	.01	311.
00.00	00.00	250	.01	.01	.01	290.
00.00	00.00	251	.01	.01	.01	270.
00.00	00.00	252	.01	.01	.01	252.
00.00	00.00	253	.01	.01	.01	235.
00.00	00.00	254	.01	.01	.01	220.
00.00	00.00	255	.01	.01	.01	205.
00.00	00.00	256	.01	.01	.01	191.
00.00	00.00	257	.01	.01	.01	178.
00.00	00.00	258	.01	.01	.01	166.
00.00	00.00	259	.01	.01	.01	155.
00.00	00.00	260	.01	.01	.01	145.
00.00	00.00	261	.01	.01	.01	135.
00.00	00.00	262	.01	.01	.01	126.
00.00	00.00	263	.01	.01	.01	118.
00.00	00.00	264	.01	.01	.01	111.
00.00	00.00	265	.01	.01	.01	107.
00.00	00.00	266	.01	.01	.01	104.
00.00	00.00	267	.01	.01	.01	101.
00.00	00.00	268	.01	.01	.01	98.
00.00	00.00	269	.01	.01	.01	95.
00.00	00.00	270	.01	.01	.01	93.
00.00	00.00	271	.01	.01	.01	91.
00.00	00.00	272	.01	.01	.01	89.
00.00	00.00	273	.01	.01	.01	86.
00.00	00.00	274	.01	.01	.01	87.
00.00	00.00	275	.01	.01	.01	85.
00.00	00.00	276	.01	.01	.01	84.
00.00	00.00	277	.01	.01	.01	83.
00.00	00.00	278	.01	.01	.01	82.
00.00	00.00	279	.01	.01	.01	81.
00.00	00.00	280	.01	.01	.01	80.
00.00	00.00	281	.01	.01	.01	80.
00.00	00.00	282	.01	.01	.01	80.
00.00	00.00	283	.01	.01	.01	79.
00.00	00.00	284	.01	.01	.01	79.
00.00	00.00	285	.01	.01	.01	79.
00.00	00.00	286	.01	.01	.01	79.
00.00	00.00	287	.01	.01	.01	79.
00.00	00.00	288	.01	.01	.01	79.

SUM 24.06 21.37 2.69 313120.
 (611.) (543.) (68.) (8866.57)

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	7155.	3822.	1087.	1087.	313087.
CMS	203.	108.	31.	31.	8866.
INCHES		18.71	21.29	21.29	21.29
MM		475.28	540.76	540.76	540.76
AC-FT		1895.	2156.	2156.	2156.
THOUS CU M		2338.	2660.	2660.	2660.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3577.	1911.	544.	544.	156543.
CMS	101.	54.	15.	15.	4433.
INCHES		9.36	13.64	13.64	10.64
MM		237.64	270.38	270.38	270.38
AC-FT		948.	1078.	1078.	1078.
THOUS CU M		1169.	1330.	1330.	1330.

●●●●●●●●●●

10

STAGE 343.90

FLOW . . . 0.00

SURFACE AREA:	O.
CAPACITY:	O.

ELEVATIONS **334.**

4

100

...

100

Figure 1

0000

120
121
122
123
124

125.
127.
128.
129.

1935
1934
1933
1932
1931
1930
1929
1928
1927
1926
1925
1924
1923
1922
1921
1920
1919
1918
1917
1916
1915
1914
1913
1912
1911
1910
1909
1908
1907
1906
1905
1904
1903
1902
1901
1900
1899
1898
1897
1896
1895
1894
1893
1892
1891
1890
1889
1888
1887
1886
1885
1884
1883
1882
1881
1880
1879
1878
1877
1876
1875
1874
1873
1872
1871
1870
1869
1868
1867
1866
1865
1864
1863
1862
1861
1860
1859
1858
1857
1856
1855
1854
1853
1852
1851
1850
1849
1848
1847
1846
1845
1844
1843
1842
1841
1840
1839
1838
1837
1836
1835
1834
1833
1832
1831
1830
1829
1828
1827
1826
1825
1824
1823
1822
1821
1820
1819
1818
1817
1816
1815
1814
1813
1812
1811
1810
1809
1808
1807
1806
1805
1804
1803
1802
1801
1800
1799
1798
1797
1796
1795
1794
1793
1792
1791
1790
1789
1788
1787
1786
1785
1784
1783
1782
1781
1780
1779
1778
1777
1776
1775
1774
1773
1772
1771
1770
1769
1768
1767
1766
1765
1764
1763
1762
1761
1760
1759
1758
1757
1756
1755
1754
1753
1752
1751
1750
1749
1748
1747
1746
1745
1744
1743
1742
1741
1740
1739
1738
1737
1736
1735
1734
1733
1732
1731
1730
1729
1728
1727
1726
1725
1724
1723
1722
1721
1720
1719
1718
1717
1716
1715
1714
1713
1712
1711
1710
1709
1708
1707
1706
1705
1704
1703
1702
1701
1700
1699
1698
1697
1696
1695
1694
1693
1692
1691
1690
1689
1688
1687
1686
1685
1684
1683
1682
1681
1680
1679
1678
1677
1676
1675
1674
1673
1672
1671
1670
1669
1668
1667
1666
1665
1664
1663
1662
1661
1660
1659
1658
1657
1656
1655
1654
1653
1652
1651
1650
1649
1648
1647
1646
1645
1644
1643
1642
1641
1640
1639
1638
1637
1636
1635
1634
1633
1632
1631
1630
1629
1628
1627
1626
1625
1624
1623
1622
1621
1620
1619
1618
1617
1616
1615
1614
1613
1612
1611
1610
1609
1608
1607
1606
1605
1604
1603
1602
1601
1600
1599
1598
1597
1596
1595
1594
1593
1592
1591
1590
1589
1588
1587
1586
1585
1584
1583
1582
1581
1580
1579
1578
1577
1576
1575
1574
1573
1572
1571
1570
1569
1568
1567
1566
1565
1564
1563
1562
1561
1560
1559
1558
1557
1556
1555
1554
1553
1552
1551
1550
1549
1548
1547
1546
1545
1544
1543
1542
1541
1540
1539
1538
1537
1536
1535
1534
1533
1532
1531
1530
1529
1528
1527
1526
1525
1524
1523
1522
1521
1520
1519
1518
1517
1516
1515
1514
1513
1512
1511
1510
1509
1508
1507
1506
1505
1504
1503
1502
1501
1500
1499
1498
1497
1496
1495
1494
1493
1492
1491
1490
1489
1488
1487
1486
1485
1484
1483
1482
1481
1480
1479
1478
1477
1476
1475
1474
1473
1472
1471
1470
1469
1468
1467
1466
1465
1464
1463
1462
1461
1460
1459
1458
1457
1456
1455
1454
1453
1452
1451
1450
1449
1448
1447
1446
1445
1444
1443
1442
1441
1440
1439
1438
1437
1436
1435
1434
1433
1432
1431
1430
1429
1428
1427
1426
1425
1424
1423
1422
1421
1420
1419
1418
1417
1416
1415
1414
1413
1412
1411
1410
1409
1408
1407
1406
1405
1404
1403
1402
1401
1400
1399
1398
1397
1396
1395
1394
1393
1392
1391
1390
1389
1388
1387
1386
1385
1384
1383
1382
1381
1380
1379
1378
1377
1376
1375
1374
1373
1372
1371
1370
1369
1368
1367
1366
1365
1364
1363
1362
1361
1360
1359
1358
1357
1356
1355
1354
1353
1352
1351
1350
1349
1348
1347
1346
1345
1344
1343
1342
1341
1340
1339
1338
1337
1336
1335
1334
1333
1332
1331
1330
1329
1328
1327
1326
1325
1324
1323
1322
1321
1320
1319
1318
1317
1316
1315
1314
1313
1312
1311
1310
1309
1308
1307
1306
1305
1304
1303
1302
1301
1300
1299
1298
1297
1296
1295
1294
1293
1292
1291
1290
1289
1288
1287
1286
1285
1284
1283
1282
1281
1280
1279
1278
1277
1276
1275
1274
1273
1272
1271
1270
1269
1268
1267
1266
1265
1264
1263
1262
1261
1260
1259
1258
1257
1256
1255
1254
12

1819.
2652.
3550.
3522.

1073.
493.
241.

2410
1220
660
470

[illegible][illegible]

.....
.....

.....
.....

STORAGE

111201103177696362

00000000000000000000000000000000

[illegible]

.....
.....

[illegible]

.....

[illegible]

၁၂၃၄၅၆၇၈၉၁၀၁၁၂၁၃၁၄၁၅၁၆၁၇၁၈၁၉၂၀၂၁၂၂၂၃၂၄၂၅၂၆၂၇၂၈၂၉၃၀
 ၃၁၃၂၃၃၃၄၃၅၃၆၃၇၃၈၃၉၄၀၄၁၄၂၄၃၄၄၄၅၄၆၄၇၄၈၄၉၅၀
 ၅၁၅၂၅၃၅၄၅၅၅၆၅၇၅၈၅၉၆၀၆၁၆၂၆၃၆၄၆၅၆၆၆၇၆၈၆၉၇၀
 ၇၁၇၂၇၃၇၄၇၅၇၆၇၇၇၈၇၉၈၀၈၁၈၂၈၃၈၄၈၅၈၆၈၇၈၈၈၉၉၀

[illegible][illegible]

000
000
000
000

[illegible][illegible][illegible]

PEAK OUTFLOW IS		3591. AT TIME		16.83 HOURS	
PEAK	3551.	6-HOUR	1898.	24-HOUR	540.
CFR	101.	12-HOUR	1559.	72-HOUR	540.
CUFS		18-HOUR	9239		15.
INCHES		236006			18.58
ACFT		91.			268.67
THOUS CU M		1161.			1071.
					1321.
					1321.
					1071.
					268.67
					10.58
					15.
					540.
					1321.
					1071.
					268.67
					18.58
					15.
					540.
					1321.
					1071.
					268.67
					10.58
					15.
					540.
					1321.
					1071.
					268.67
					18.58
					15.
					540.
					1321.
					1071.
					268.67
					10.58
					15.
					540.
					1321.
					1071.
					268.67
					18.58
					15.
					540.
					1321.
					1071.
					268.67
					10.58
					15.
					540.
					1321.
					1071.
					268.67
					18.58
					15.
					540.
					1321.
					1071.
					268.67
					10.58
					15.
					540.
					1321.
					1071.
					268.67
					18.58
					15.
					540.
					1321.
					1071.
					268.67
					10.58
					15.
					540.
					1321.
					1071.
					268.67
					18.58
					15.
					540.
					1321.
					1071.
					268.67
					10.58
					15.
					540.
					1321.
					1071.
					268.67
					18.58
					15.
					540.
					1321.
					1071.
					268.67</

SUMMARY OF DAM SAFETY ANALYSIS

.....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 343.60 55. :0.	SPILLWAY CREST 343.90 60. 0.	TOP OF DAM 345.90 95. 1076.	TIME OF MAX HOURS	TIME OF FAILURE HOURS
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER HOURS	TIME OF FAILURE HOURS
.50	347.20	1.30	121.	3551.	4.83	16.83
.40	346.91	1.01	115.	2837.	3.92	16.83
.30	346.56	.66	108.	2123.	2.67	16.83
.20	346.14	.24	100.	1398.	1.25	16.92
.10	345.32	0.00	85.	1673.	0.00	17.00

APPENDIX 5

Bibliography

1. "Recommended Guidelines for Safety Inspection of Dams," Department of the Army, Office of the Chief of Engineers, Washington, D.C. 20314.
2. Design of Small Dams, Second Edition, United States Department of the Interior, Bureau of Reclamation, United States Government Printing Office, Washington, D.C., 1973.
3. Holman, William W. and Jumikis, Alfreds R., Engineering Soil Survey of New Jersey, Report No. 2, Essex County, Rutgers University, New Brunswick, N.J., 1953.
4. "Geologic Map of New Jersey," prepared by J. Volney Lewis and Henry B. Kummel, dated 1910 - 1912.
5. Chow, Ven Te., Ed., Handbook of Applied Hydrology, McGraw-Hill Book Company, 1964.
6. Herr, Lester A., Hydraulic Charts for the Selection of Highway Culverts, U.S. Department of Transportation, Federal Highway Administration, 1965.
7. Safety of Small Dams, Proceedings of the Engineering Foundation Conference, American Society of Civil Engineers, 1974.
8. King, Horace Williams and Brater, Ernest F., Handbook of Hydraulics, Fifth Edition, McGraw-Hill Book Company, 1963.

DATE
FILMED
—8